

重量内訳明細<階及び部材、太さ別出力>

工事名: (仮称)***** 新築工事

階	部材	径		D10	D13	D16	D19	D22	D25	D29	D32	D32	D35	D35	D41	合計
		SD295	SD295	SD295	SD345	SD345	SD345	SD390	SD490	SD490/定着板	SD490	SD490/定着板	SD490			
基礎	基礎		282	9,536												9,818
	柱	156	22	74					1,090	1,613			13,952		2,719	19,626
	床版		3,804		97											3,901
	壁	460		151												611
1F	柱	26	12	41					258	605	896		10,223		1,802	13,863
	大梁	875	6,341	31,327							404		21,791	20,683		81,421
	小梁	247						1,120								1,367
	床版	1,156	7,505													8,661
	壁	3,793	1,528	1,598	16,579											23,498
	階段	203	168													371
2F	柱								344				7,982			8,326
	大梁	380	2,755						6,332				7,308	7,158		23,933
	大梁フカシ	66		103												169
	小梁	284		329			754									1,367
	床版	3,056	9,526	254	65											12,901
	壁	3,436	3,286	14,808												21,530
	階段	175	143													318
3F	柱				326			316					6,874			7,516
	大梁	376	1,079	593	907			1,175					8,266	5,880		18,276
	小梁	108		336												444
	床版	5,022	6,461	8,188	65											19,736
	壁	3,276	2,868	13,368												19,512

重量内訳明細<階及び部材、太さ別出力>

工事名: (仮称)***** 新築工事

階	部材	径		D10	D13	D16	D19	D22	D25	D29	D32	D32	D35	D35	D41	合計
		SD295	SD295	SD295	SD345	SD345	SD345	SD390	SD490	SD490/定着板	SD490	SD490/定着板	SD490			
3F	階段	175	143													318
4F	柱						512						4,321			4,833
	大梁	376	1,079	593	907			1,175					8,266	5,880		18,276
	小梁	108		336												444
	床版	5,022	6,461	8,188	65											19,736
	壁	2,909	4,883	8,960												16,752
	階段	175	143													318
5F	柱						407						4,438			4,845
	大梁	376	1,079	593	907			1,175					8,266	5,880		18,276
	小梁	108		336												444
	床版	5,022	6,461	8,188	65											19,736
	壁	2,908	5,968	6,890												15,766
	階段	175	143													318
6F	柱						420						4,042			4,462
	大梁	376	1,079	593	907			1,175					8,266	5,880		18,276
	小梁	108		336												444
	床版	5,021	6,465	8,188	65											19,739
	壁	2,908	9,085	4,576												16,569
	階段	173	143													316
7F	柱						389						3,643			4,032
	大梁	376	1,079	593	907			1,175					8,266	5,880		18,276
	小梁	108		336												444

重量内訳明細<階及び部材、太さ別出力>

工事名: (仮称)***** 新築工事

階	部材	径												合計
		D10 SD295	D13 SD295	D16 SD295	D19 SD345	D22 SD345	D25 SD345	D29 SD390	D32 SD490	D32 SD490/定着板	D35 SD490	D35 SD490/定着板	D41 SD490	
7F	床版	5,021	6,465	8,188	65									19,739
	壁	2,906	10,657	2,554										16,117
	階段	173	143											316
8F	柱		76		389				2,737					3,202
	大梁	376	1,079	593	907		1,175				8,140	5,975		18,245
	小梁	108		336										444
	床版	5,021	6,465	8,188	65									19,739
	壁	6,484	4,906	824										12,214
	階段	173	143											316
9F	柱		150		362				2,110					2,622
	大梁	362	1,079	593	907		1,175				6,278	4,903		15,297
	小梁	108		336										444
	床版	5,020	6,465	8,185	65									19,735
	壁	6,514	4,932	824										12,270
	階段	173	143											316
10F	柱		76		384				2,154					2,614
	大梁	350	1,050	593	907		1,175				6,061	5,209		15,345
	小梁	108		336										444
	床版	5,046	6,506	8,185	65									19,802
	壁	6,060	3,805	713										10,578
	階段	173	143											316
11F	柱		144		377			1,487	184					2,192

重量内訳明細<階及び部材、太さ別出力>

工事名: (仮称)**** 新築工事

階	部材	径	D10	D13	D16	D19	D22	D25	D29	D32	D32	D35	D35	D41	合計
		SD295	SD295	SD295	SD345	SD345	SD345	SD390	SD490	SD490/定着板	SD490	SD490/定着板	SD490		
11F	大梁		358	1,024	593	907		1,175				6,380	4,636		15,073
	小梁		108		336										444
	床版		5,046	6,506	8,185	65									19,802
	壁		6,060	3,805	713										10,578
	階段		173	143											316
12F	柱			76		378			1,734						2,188
	大梁		325	904	593	907		1,175		4,564	3,203				11,671
	小梁		108		336										444
	床版		5,046	6,506	8,185	65									19,802
	壁		5,828	3,384	713										9,925
	階段		173	143											316
13F	柱					386			1,728						2,114
	大梁		319	785	593	892		1,175		3,760	3,007				10,531
	小梁		108		336										444
	床版		5,054	6,512	8,202	65									19,833
	壁		5,880	3,445	713										10,038
	階段		173	143											316
14F	柱					360		956	398						1,714
	大梁		307	2,004	593	892		1,175		3,229	2,447				10,647
	小梁		108		336										444
	床版		5,140	6,576	8,292	65									20,073
	壁		6,629	3,019	610										10,258

重量内訳明細<階及び部材、太さ別出力>

工事名: (仮称)***** 新築工事

階	部材	径	D10	D13	D16	D19	D22	D25	D29	D32	D32	D35	D35	D41	合計
		SD295	SD295	SD295	SD345	SD345	SD345	SD390	SD490	SD490/定着板	SD490	SD490/定着板	SD490		
14F	階段		173	143											316
15F	柱					251		916							1,167
	大梁		306	2,923	606	892		1,175	4,895						10,797
	小梁		108		336										444
	床版		5,162	6,563	8,323	65									20,113
	壁		8,166	3,138	641										11,945
RF	大梁		294	2,015	595	908		1,388	3,772						8,972
	小梁		108		336										444
	床版		5,523	3,603	9,036	65									18,227
	壁		1,835	790											2,625
設備基礎	基礎		46	32										78	
人通孔補強	大梁				206					583				789	
荷揚開口補	床版			3,019											3,019
合計		162,359	211,619	229,268	35,246	1,874	25,785	15,709	22,234	8,657	152,763	77,964	4,521	947,999	